

Item	Description	Qty	Unit	Rate	Total GH¢
	BILL NO. 1				
	<u>REHABILITATION OF ASSEMBLY OFFICE COMPLEX (OFFICE REPAIR WORKS, BAC OFFICE, CONSTRUCTION OF 2NO.3-UNIT GARAGE AND FURNISHING)</u>				
	SUBSTRUCTURE				
	<u>Excavation and Earthworks</u>				
A	Excavate pit not exceeding 1.5 metres deep ditto	1	m ³		
	<u>Plain in-situ concrete (1:4:8-20mm aggregate) in;</u>				
B	Foundation	1	m ³		
	SUBSTRUCTURE				
	Carried to Summary				
	<u>H72: ALUMINIUM SHEET COVERING/FLASHINGS</u>				
	<u>Raincoat or equally approved Longspan aluminium, corrugated sheets; pre-painted; standard profile; 0.50mm gauge, two corrugations side laps, 150mm end laps; bedded with mastic sealing strips</u>				
C	Roofing coverings; fixing to timber purlins at 1050mm general spacing with galvanised drive screws, nuts, washers, caps; drilling holes; pitch 10 degrees	121	m ²		
	<u>COVERING</u>				
	Carried to Summary				
	<u>STRUCTURAL/CARCASSING METAL/TIMBER</u>				
	<u>G20: CARPENTRY/TIMBER FRAMING/FIRST FIXING</u>				
	<u>Hardwood; treated with preservative; sawn</u>				
D	50 x 150mm Rafters	103	m		
E	50 x 100mm Purlins	128	m		
F	Fescia board	50	m		
	<u>Carpenter's Metalwork</u>				
F	mold and fabrication of 75mm galvanised pipe as stanchion	15	No		
	CARPENTRY				
	Carried to Summary				
	<u>SUMMARY</u>				
	SUBSTRUCTURE WORK				
	ROOFING				
	CARPENTRY				
	<u>TOTAL</u>				
	CARPORT CARRIED GENERAL SUMMARY				

Item	Description	Qty	Unit	Rate	Total GH¢
	EXTERNAL WORKS				
	<u>APRON</u>				
	<u>Excavation and Earthworks</u>				
A	Excavate trench not exceeding 1.50m metres deep commencing 150mm below ground level	10	m ³		
B	Return, fill in and well ram selected excavated material around foundation	4	m ³		
C	Remove surplus excavated material from site	7	m ³		
	<u>Hardcore as described, spread, levelled and well rammed and consolidated</u>				
D	Filling in layers not exceeding 225mm thick in making up levels under floors.	8	m ³		
	<u>Concrete Work</u>				
E	Plain in-situ concrete (1:3:6-40mm aggregate) as described foundation in trenches	4	m ³		
F	Concrete Slab	2	m ³		
	Formwork Sawn formwork to				
G	Edge of slab, 100mm wide	45	m		
	<u>Blockwork</u> <u>Sandcrete blockwork in cement and sand (1:4) mortar</u>				
H	125mm thick solid wall	40	m ²		
J	20mm Cement and sand render to wall	35	m ²		
K	Prepare and apply three coats of emulsion paint on rendered wall	36	m ²		
	<u>DEMOLITION</u>				
L	Include a provisional sum of GH¢4,500.00 for demolition of existing apron and disposal of debris and its associated works.	1	sun		
	<u>BILL NO.4: EXTERNAL WORKS (APRON)</u>				
	Carried to General Summary				

Item	Description	Qty	Unit	Rate	Total GH¢
	<u>RENOVATION OF ASSEMBLY COMPLEX AND BAC OFFICE</u>				
	<i>Ceramic floor tiles: 3mm joints,symmetrical layout fixing with adhesive cement; grouting with matching coloured grout</i>				
M	400 x 400 x 6mm thick porcelain floor tiles including extra for round edges bedded and jointed in cement and sand mortar (1:4) and pointed in mixture of white cement on floated backing on floor	60	m²		
N	Skirting height 75mm	45	m		
P	Include a provisional sum of GH¢7,00.00 for chesilling of crack and removal of debries and it associated works including make good the affected surface.	1	sun		
Q	Include a provisional sum of GH¢5,000.00 for repair of sanitray appliances	1	sun		
	<u>PLUMBING AND ENGINEERING INSTALLATIONS</u>				
R	replacement of W.C Complete (Twyford)	4	no		
	<u>TOTAL</u>				
	Renovation Carried to General Summary				
	<u>FURNITURES</u>				
S	Include a provisional sum of GH¢100,000.00 for supply of office furniture for Assembly Offices	1	item	100,000.00	
N	Supply and Installation of 2.0 HP Air-Condition	2	no		
U	Supply and Installation of 2.5 HP Air-Condition	1	no		
S	Supply and Installation of 1.5 HP Air-Condition	2	no		
	<u>TOTAL</u>				
	Furniture Carried to General Summary				
	<u>GENERAL SUMMARY</u>				
	EXTERNAL WORKS (APRON)				
	RENOVATION OF ASSEMBLY COMPLEX AND BAC OFFICE				
	FURNITURE				
	ELECTRICALS WORKS				
	CARPORT CARRIED GENERAL SUMMARY				
	PAINTING				
	<u>TOTAL</u>				