

PUBLIC WORKS DEPARTMENT

Item	Description	Qty	Unit	Rate GH¢	Amount GH¢
	<u>REHABILITATION OF STOREY BUILDING AT WA FOR THE ATTORNEY-GENERAL'S DEPT. - WA UPPER WEST REGION</u>				
	<u>ROOFING</u> <u>Roof Repairs</u>				
A.	Including a provisional Sum of Eighteen Thousand, Eight Hundred Ghana Cedis for checking roof members and long-span aluminium roofing sheet as approved equal	Item			
	<u>ROOFING</u> <i>Carried To Summary</i>				
	<u>JOINERY</u> <u>Doors</u> <u>Wrot Hardwood:</u>				
B.	44mm{Finished} Panel door comprising 100mm stiles, top and middle rails, 150mm bottom rail with 6No. Hardwood panes in single-leaf, size 750 x 2050mm high	14	No.		
	Ditto double door	1	No.		
	<u>Fillets, Glazing Beads And Grounds</u> <u>Well Seasoned Wrought Hardwood In:-</u>				
C.	1mm x 50mm Door stop	18	m		
	<u>Ironmongery</u> <u>Supply and fix the following Ironmongries with screws to hardwood:-</u>				
D.	<u>1½ Pair</u> 100m heavy duty brass butt hinges	14	No.		
E.	75mm Double security mortice lock do. [Italian Made]	14	No.		
	<u>JOINERY</u> <i>Carried To Summary</i>				
		1			

PUBLIC WORKS DEPARTMENT

Item	Description	Qty	Unit	Rate GH¢	Amount GH¢
	<u>PLUMBING INSTLLATION</u>				
	<u>Sanitary Fittings</u>				
	<u>Supply and fix the following Sanitary Fittings</u>				
A.	Low level w.c suite complete with ceramic cistern "Twyford" or any other equal approved	5	No.		
B.	Wash hand basin complete with 2No. 12mm chromium plated taps, 31mm bottles trap, plug chain and stay "Twyford" or any other equal approved	5	No.		
C.	White fibre glass bath complete with telephone shower, waste union, hot and cold mixer tap [Ariston Brand]	5	No.		
D.	Stainless steel kitchen sink with double-bowl and double drainier complete with 40mm chromium plated waste fittings and plugs	1	No.		
E.	Shower fittings complete with 12mm diameter rose	5	No.		
F.	Chromium plated toilet roll holder with cover plugged and screwed to wall	2	No.		
G.	Chromium plated towel rail 900mm long do.	5	No.		
	<u>PIPE WORKS</u>				
H.	Include the Provisional Sum of One Thousand and Forty Ghana Cedis for all pipe works and the rehabilitation of existing water tank stand	Item			
	<u>PLUMBING INSTALLATION</u>				
	<i>Carried To Summary</i>				
		2			

PUBLIC WORKS DEPARTMENT

Item	Description	Qty	Unit	Rate GH¢	Amount GH¢
	<u>ELECTRICAL INSTALLATION</u>				
A.	Include the Provisional Sum of Twenty-Five Thousand, Three Hundred and Twenty Ghana Cedis for re-wiring of the whole building and Air-conditions	Item			
	<u>ELECTRICAL INSTALLATION</u> <i>Carried To Summary</i>				
	<u>GLAZED DOOR/WINDOWS</u>				
B.	Include the Provisional Sum of One Thousand, Three Hundred and Twenty Ghana Cedis for Cleaning of 3-bay sliding windows, single leaf doors and double door	item			
	<u>GLAZED DOOR/WINDOWS</u> <i>Carried To Summary</i>				
	<u>PAINTING AND DECORATING</u> <u>Prepare and apply three Coats of Emulsion</u> <u>Paint on:</u>				
C.	Internal rendered wall surfaces	175	m ²		
D.	External rendered wall surfaces	158	m ²		
E.	Plywood soffit	68	m ²		
F.	Screen wall surfaces	12	m ²		
	Total C/F				
		3			

PUBLIC WORKS DEPARTMENT

Item	Description	Qty	Unit	Rate GH¢	Amount GH¢
	Total B/F				
A.	Rendred Fascia board	58	m ²		
	<u>Scrape off, rub-down, prepare and apply three coats of hardgloss oil paint to previously painted surfaces:-</u>				
B.	Hardwood general surfaces	38	m ²		
C.	Ditto not exceeding 300mm girth	32	m ²		
	<u>PAINTING AND DECORATING</u>				
	<i>Carried To Summary</i>				
	<u>S U M M A R Y</u>				
	ROOFING				
	JOINERY				
	PLUBLING INSTALLATION				
	ELECTRICALS INSTALLATION				
	GLAZED DOOR/WINDOWS				
	PAINTING AND DECORATING				
	TOTAL ESTIMATES				
		4			