

[illegible]

	CONCRETE OVERHEAD STAND				
	SUBSTRUCTURE				
A	Excavate pit to receive column bases average depth not 150mm commencing fromstripped level	10	CM		
B	Backfill selected excavated material around foundation	6	CM		
C	Remove surplus excavated material from site	4	CM		
	<i>Plain insitu concrete 1:4:8-20mm agg as described :</i>				
D	50mm Thick blinding	5	SM		
	<i>Reinforced insitu vibrated concrete 1:2:4 19mm agg. as described in:</i>				
E	Column base	2	CM		
F	Column	1	CM		
	<i>Mild steel round bar reinforcement to BS 4449</i>				
G	16mm Diameter bars in column bases	98	KG		
H	20mm Diameter bars in columns	95.00	KG		
J	10mm Ditto as stirrups	13	KG		
	C/F				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	B/F				
	<u>Sawn formwork to:</u>				
A	Vertical sides of columns	10	SM		
	SUBSTRUCTURE				
	CARRIED TO SUMMARY				
	<u>SUPERSTRUCTURE</u>				
	<u>Reinforced insitu vibrated concrete 1:2:4</u>				
	<u>19mm agg. as described in:</u>				
B	Column	2	CM		
C	Beams	2	CM		
D	Suspended floor slab	9	SM		
	<u>Mild steel round bar reinforcement to</u>				
	<u>BS 4449</u>				
E	20mm Diameter bars in column	980	KG		
F	10mm Ditto as stirrups in column	445	KG		
G	16mm Diameter bars in Beams	880	KG		
H	10mm Ditto as stirrups in beams	318	KG		
I	12mm Diameter bars in Suspended floor slab	780	KG		
	<u>Sawn formwork as described to:</u>				
J	Vertical sides of column	14	SM		
K	Sides and soffit of horizontal beam	8	SM		
	C/F				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A	B/F	10	SM		
	Sides and soffit of suspended floor slab				
	SUPERSTRUCTURE CARRIED TO SUMMARY				
B	METAL WORKS	63	LM		
	50mm round galvanized pipe framed with 50mm round pipe vertical dividing strips including all ironmongery as :				
	Guard rails				
C	METAL WORK CARRIED TO SUMMARY	1	NO		
	PLUMBING WORKS				
	Supply and install 10,00cu Litres reservoir				
	PLUMBING WORKS CARRIED TO SUMMARY				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	SUMMARY				
A	BOREHOLE DRILLING AND MECHANIZATION				
B	SUBSTRUCTURE				
C	SUPERSTRUCTURE				
D	METAL WORKS				
E	PLUMBING WORKS				
	SUMMARY				

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	GENERAL SUMMARY SUBTOTAL 1 FOR 1 SITE(LOCATION) MULTIPLY BY 3 NO.SITES SUBTOTAL 2 ADD 5% FOR PRILIMINARIES SUB TOTAL 3 GRAND TOTAL CARRIED TO TENDER FORM		NO		