LINE ROUTE FOR THE PROPOSED 11kV NEW TEMA LINE.

1. The green sections represent the underground power cable and the white section, the overhead line.

2. The line from the New Tema SS to the first Overhead line pole (Gantry-AP2) is about 335metres.

3. The overhead line length is about 2km

4. The last mile to the existing overhead pole at the Volta SS (AP5-AP6) is about 95metres.

5. There would be 2 road crossings.

6. A second underground cable is proposed from the Volta SS to the SCC yard. The distance measured is about 400m.


A-HEAD OFFICE
AP6
AP5
AP4
AP3
AP2
AP 1
GANTRY
Steel Works Rd
Steel Works R